

CASE STUDY



INSTALLATION DATE:
March 2016

END USER:
VIVA Energy Australia (Formerly Shell Geelong)

LINES SIZES AND MATERIAL:
1 ½" SCH40, 2" SCH40 & 3" SCH40
NPS Stainless Steel 316L

SYSTEM MEDIUM:
Oily Wastewater

SYSTEM TEMPERATURE:
Ambient

SPECIAL COMMENTS OR NOTES:
Test Pressure at 30BAR for 2hours with no leaks.

Trenches will now be filled in with concrete to bury the lines.



